

## **Service Kit**

Title: Bell 429 Air Conditioner Condenser Blower Motor Upgrade

**Date:** July 25, 2025

**Applicability:** Bell Helicopter Model 429 Equipped with the Air Comm Corporation

429EC-200 and -202 Air Conditioning Systems

**Reference:** FAA / STC # SR00693DE, Bell Helicopter 429 Air Conditioning System

#### Introduction:

This document provides for an air conditioning system improvement for aircraft operating in extreme environments by the replacement of the existing condenser blower with a blower that provides a higher condenser performance. This document also provides information for modifying the supporting electrical wiring to accommodate the slightly higher power draw of the new blower.

### Approval:

The information provided within this document is based on FAA approved data.

### Weight & Balance:

The weight change due to the installation of these parts is not significant and so no adjustment to the weight and balance of the aircraft is necessary. The high performance blower change results in a 2.6 lb. weight increase.

**NOTE:** SB 429-206 will need to be ordered from Air Comm and installed with this service kit. Contact Air Comm service department to order part number SB 429-206.

### Kit Identification:

There are differences in the relay panel wiring between earlier and later versions of the air conditioner and the technician must first correctly determine which version of the system is installed.

System Kit No.	System Type	Electrical Installation	Relay Panel P/N
429EC-200-1	Dual Evaporator (2 Fwd, 2 Aft)	429EC-810-1	429EC-8424-1
429EC-200-3	Dual Evaporator (2 Fwd, 2 Aft)	429EC-810-2	429EC-8424-2
429EC-200-5	Dual Evaporator (2 Fwd, 2 Aft)	429EC-810-2	429EC-8424-2
429EC-200-6	Dual Evaporator (2 Fwd, 2 Aft)	429EC-810-2	429EC-8424-2
429EC-202-1	Single Evaporator (1 Fwd, 1 Aft)	429EC-812-1	429EC-8424-2
429EC-202-3	Single Evaporator (1 Fwd, 1 Aft)	429EC-812-1	429EC-8424-2
429EC-202-4	Single Evaporator (1 Fwd, 1 Aft)	429EC-812-1	429EC-8424-2

## **Revision History:**

Revision	Issue Date	Inserted By	Approved by	Description of Changes
NC	6/23/15	BD	KP	Initial Release
Α	6/30/15	JB	KP	Added support for older systems
В	7/22/15	JMB	KP	Updated the Introduction
С	10/14/15	JMB	KDP	For the -2 relay panel mod: qty of S-8509EC-1 was 2, added the S-8509EC-2 wire set
D	3/26/21	ROL	BDD	All Pages: Updated company address. Page 1: Added Note SB 429-206. Pages 2, 3 & 7: S-6085EC-3 was S-6085EC-2 (now Obsolete).
E	7/25/2025	TLW		Updated footer information. Added required parts from SB 429-206 to this documents BOM and clarified the installation instruction. Added part marking to the instructions. Added 1.5 to configuration change line.

### **Bill of Materials:**

Parts to be removed and discarded (all systems)

Item	Part Number	Description	Quantity
1	S-6063EC-1,-2,-3	Condenser Fan Assembly	1
2	MS26574-20	20A Circuit Breaker	1

Parts to be installed (Systems with 429EC-8424EC-1 Relay Panels)

Item	Part Number	Description	Quantity
1	S-6085EC-3	Condenser Fan Assembly	1
2	MS20426AD4-5	Rivet, Solid, Countersunk 100 Degree	8
3	MS21059L5	Nutplate, Floating, Two Lug	4
4	MS26574-25	25A Circuit Breaker	1
5	S-8509EC-1	ACJ2-K1 wire set #1	1
6	S-8509EC-2	ACJ2-K1 wire set #2	1
7	ES39019-1	Locking Fastener	4
		Install per document SB 429-206	

Parts to be installed (Systems with 429EC-8424EC-2 Relay Panels)

Item	Part Number	Description	Quantity
1	S-6085EC-3	Condenser Fan Assembly	1
2	MS20426AD4-5	Rivet, Solid, Countersunk 100 Degree	8
3	MS21059L5	Nutplate, Floating, Two Lug	4
4	MS26574-25	25A Circuit Breaker	1
5	S-8509EC-1	ACJ2-K1 wire set #1	1
6	S-8509EC-2	ACJ2-K1 wire set #2	1
7	S-8511EC-1	ACJ2-Term Block wire set	2
8	ES39019-1	Locking Fastener	4
		Install per document SB 429-206	

### 1.0 Work Instructions

### 1.1 Condenser Fan:

# Removal: (See Figure 1)

### **CAUTION**

Disconnect the aircraft battery and external power prior to starting work. Recover the refrigerant charge from the system prior to starting work.

- 1. Disconnect, cap, and stow any air conditioning plumbing tubes or hoses that interfere with the removal of the condenser fan.
- 2. Remove the cabin evaporators. Refer to the Instructions for Continued Airworthiness (ICA) 429EC-200M-1 for instructions.
- 3. Disconnect the blower electrical connector (see Fig. 1).
- Remove 4 each MS21044N04 nuts, 8each NAS1149DN432J washers, & 4each MS35206-215 screws from the electrical plug and remove the plug from its retaining bracket.
- 5. Remove 2 each MS27039-0808 screws, 2 each NAS1149FN832P Washers, & 2 each MS21919WDG6 clamps holding the blower wires to the condenser housing.
- 6. Remove 4 each AN5-7A bolts holding the S-6063EC-1,-2,-3 condenser blower assembly.
- 7. Remove the S-6063EC-1,-2,-3 condenser blower assembly.
- 8. Fill the 4 exposed blower mounting holes in the condenser shroud with RTV 100 series black silicone adhesive.

# Installation: (See Figure 2)

NOTE: Newer air conditioners use a condenser housing containing the provisional mounting holes and nutplates to accept the high-performance blower.

- 1. If the S-6085EC-3 condenser blower assembly mounting holes are not pre-existing in the condenser housing, locate the new mounting holes using the new S-6085EC-3 condenser blower assembly as a template by centering it over the existing blower opening in the condenser housing and transferring the holes.
  - a. Install 4 each MS21059L5 nutplates using 8 each MS20426AD4-5 Rivets.
- 2. Remove any RTV from the mounting holes if present.
- 3. Fit the condenser blower into place.

- 4. Do not re-install the previously removed 4 each AN5-7A bolts. Follow the instructions in document SB 429-206 to install 4 each ES39019-1 Locking Fasteners in the 4 mounting locations to secure the blower in place.
- 5. Secure the wires using previously removed clamps.
- 6. Locate the existing part marking 429EC-7004-1,-2,-3 on the full condenser assembly and with indelible ink add next to it part markings "SK-429EC-7000" and "SB 429-206" and "429EC-7006-3" to indicate the blower change to the condenser assembly.
- 7. Install the electrical plug to the retaining bracket using 4 each MS21044N04 Nuts, 8 each NAS1149DN432J washers, & 4 each MS35206-215 screws previously removed.
- 8. Reconnect the blower electrical connector.
- 9. Reinstall the cabin evaporator/s per instructions in ICA 429EC-200M-1.
- 10. Reconnect any tubes or hoses that were removed.
- 11. Perform a vacuum test and system service in accordance with ICA 429EC-200M-1.

## 1.2 Circuit Breaker: (See Figures 3, 4)

### Removal:

1. Remove 1 each MS26574-20 20 AMP circuit breaker located at the "COND" position in the RH Non Essential Bus.

### Installation:

1. Install 1 each MS26574-25 25 AMP circuit breaker at the "COND" location in the RH Non-Essential Bus.

# 1.3 429EC-8424-1 Relay Panel Upgrade: (See Figures 3, 5)

### Removal:

- 1. Locate the 429EC-8424-1 Relay Panel Box. Disconnect the external connections and remove the box.
- 2. Referring to electrical schematic Figure 5, remove wire between Pin A at the ACJ2 receptacle and pin B1 at the K1 relay.
- 3. Remove wire between Pin H at the ACJ2 receptacle and pins A2 & B2 at the K1 relay.

### Installation:

- 1. Install 1each supplied S-8509EC-1 wire set between Pin A at the ACJ2 receptacle and pins B1 & C1 at the K1 relay.
- 2. Install 1 each supplied S-8509EC-2 wire set between Pin H at the ACJ2 receptacle and pins A2, B2 & C2 at the K1 relay. Note that the smaller, 16 ga wire must be inserted into position A2 on K1 and the 14 ga wires must be inserted into B2 & C2.
- 3. Locate the existing part marking and with indelible ink add next to it part marking "SK-429EC-7000" to indicate the upgrade to the relay panel box.
- 4. Replace the 429EC-8424-1 Relay Panel Box and re-mate the electrical connections.
- 5. Apply aircraft electrical power and verify operation of the condenser blower.

# 1.4 429EC-8424-2 Relay Panel Upgrade: (See Figures 3, 6)

### Removal:

- 1. Locate the 429EC-8424-2 Relay Panel Box. Disconnect the external connections and remove the box.
- 2. Referring to electrical schematic Figure 5, remove wire between Pin A at the ACJ2 receptacle and pins B1 & C1 at the K1 relay.
- 3. Remove wire between Pin H at the ACJ2 receptacle and pins B2 & C2 at the K1 relay.
- 4. Remove wire set from ACJ2 pins D & P and the terminal block.
- 5. Remove wire set from ACJ2 pins R & T and the terminal block.

### Installation:

- 1. Install 1 each supplied S-8509EC-1 wire set between Pin A at the ACJ2 receptacle and pins B1 & C1 at the K1 relay.
- 2. Install 1 each supplied S-8509EC-1 wire set between Pin H at the ACJ2 receptacle and pins B2 & C2 at the K1 relay.
- 3. Install 1 each supplied S-8511EC-1 wire set from ACJ2 pins D & P receptacle and the terminal block. Note that pin D receives the 12 ga. wire, and pin P receives the 14 ga. wire.
- 4. Install 1 each supplied S-8511EC-1 wire set from ACJ2 pins R & T receptacle and the terminal block. Note that pin T receives the 12 ga. wire, and pin R receives the 14 ga. wire.
- 5. Locate the existing part marking and with indelible ink add next to it part marking "SK-429EC-7000" to indicate the upgrade to the relay panel box.

- 6. Replace the 429EC-8424-2 Relay Panel Box and re-mate the electrical connections.
- 7. Apply aircraft electrical power and verify operation of the condenser blower.

## 1.5 Configuration Change:

- 1. Record in the aircraft logbook that the air conditioning has been upgraded to one of the following new configurations:
  - a. **429EC-200-7** if your original system was a 429EC-200-1,-3,-5,-6.
  - b. **429EC-202-5** if your original system was a 429EC-202-1,-3,-4.




Figure 1. Existing blower on the condenser assembly




Figure 2. High performance blower on the condenser assembly





Figure 3. Circuit Breaker panel and Air Conditioning Relay Panel Box



Figure 4. Circuit Breaker panel







Figure 5. 429EC-8424EC-1 Relay Panel Box Wiring, existing and modified






Figure 6. 429EC-8424EC-2 Relay Panel Box Wiring, existing and modified